

Manistee County Road Commission Bid Forms and Requirements for High Bridge Road 2026

Page 1 of 4

SEALED PROPOSALS (BIDS) WILL BE RECEIVED UNTIL 1:00 PM, EDT, MONDAY, October 12, 2026 by the Board of County Road Commissioners of the County of Manistee, 8946 Chippewa Highway, Manistee, Michigan 49614.

BID REQUIREMENTS:

SIR: The undersigned has examined the location(s) of the work described herein and is fully informed as to the nature of the work and conditions relating to its performance and understands the quantities shown are approximate and are subject to either increase or decrease.

The undersigned hereby proposes to furnish all necessary equipment, tools, apparatus, and other means of construction, do all of the work, furnish all materials except as otherwise specified herein; and, for the unit prices named in the attached **Itemized Bid Form**, to complete the work herein described in strict accordance with the plans and the requirements of these bid documents.

The undersigned further proposes to perform extra work (for items that are not included with the itemized form) that may be authorized by the Manistee County Road Commission (MCRC). Compensation for extra work will be made on the basis of an agreed upon unit price prior to performing the extra work.

SPECIFICATIONS AND PLANS:

All materials, equipment, and construction methods used on the project(s) shall be in accordance with the applicable sections of the Michigan Department of Transportation (MDOT) 2020 Standard Specifications for Construction, MDOT supplemental specifications, and the attached plans, special provisions, and other bid documents.

PROGRESS SCHEDULE:

MCRC anticipates that construction can begin no earlier than **October 19, 2026**. In no case shall any work be commenced prior to receiving notice of award of contract from MCRC.

The Contractor must submit a complete, detailed and signed MDOT Form 1130, Progress Schedule, to the Engineer within seven (7) calendar days after award and prior to starting work. The Progress Schedule must include, as a minimum, the controlling work items for the completion of the project, as well as the planned dates or work days that these work items will be the controlling operations.

The entire project must be completed on or before the final project completion date of **December 11, 2026**. Failure to complete all pay items by the completion

Manistee County Road Commission Bid Forms and Requirements for High Bridge Road 2026

Page 2 of 4

date will result in the Contractor being assessed Liquidated Damages in accordance with subsection 108.10 of the Standard Specifications for Construction.

Work delays due to "Labor disputes" as shown in subsection 108.08.C.6 of the Standard Specifications for Construction will not be considered as an "excusable delay without liquidated damages" in the granting of time extensions to the completion date for the project. The Contractor will be assessed Liquidated Damages in accordance with subsection 108.10 of the Standard Specifications for Construction should the project work be delayed due to a labor dispute.

After award and prior to the start of the work, the Contractor must attend a preconstruction meeting with the Engineer and the Owner (Manistee County Road Commission) at the MCRC. The Engineer will arrange the day and time for the meeting.

BID GUARANTEES:

The undersigned enclosed a certified or cashier's check on an open solvent bank, or bid bond, in the amount of not less than \$2,000.00 payable to the Manistee County Board of Road Commissioners as a guarantee of good faith. If the undersigned is the successful bidder, and fails to enter into a contract or to furnish satisfactory bonds to the Board of Manistee County Road Commissioners within fifteen (15) days after being furnished with the necessary contract and bond forms, said check, or bid bond, shall be forfeited to the Board of County Road Commissioners as liquidated damages. It is understood that the check, or bid bond, of the selected bidder will not be returned until the contract has been executed, and that the proposal guarantees of all except the selected bidder will be returned promptly.

This bid guarantee will cover all projects shown in these bid documents.

INSURANCE REQUIREMENTS:

The successful bidder shall furnish proof of standard Owner's Protective Liability and Owner's Protective Property Damage Liability Insurance within ten days upon notification of award of the Contract and prior to beginning work on the project(s). The following minimum requirements must be included on the certificate of insurance:

**Manistee County Road Commission
Bid Forms and Requirements for
High Bridge Road 2026**

Page 3 of 4

Bodily Injury or Death Liability:

Each Person.....	\$500,000
Each Occurrence.....	\$1,000,000
Aggregate.....	\$2,000,000

Property Damage and Physical Damage to Property Liability:

Each Occurrence.....	\$1,000,000
Aggregate.....	\$2,000,000

The permittee or contractor shall name the MCRC as additional insured, by name on the certificate of insurance worded as follows:

“The Board of Manistee County Road Commissioners, the Manistee County Road Commission, and their officers, agents, and employees, are named as additional insured parties.”

The policy shall state that the MCRC must be given thirty (30) days written notice before said insurance is altered or cancelled.

DELAYED ACCEPTANCE, FINAL INSPECTION, AND PAYMENT TO CONTRACTOR:

The MCRC Manager and/or Construction Supervisor (or designated representatives) will inspect the project with the Contractor after all work is completed, a minimum of one (1) week prior to the final project completion date. If deficiencies are found, corrective work is required. Complete all corrective work by the final project completion date, or by an agreed upon date. All costs associated with completing this corrective work, to the satisfaction of the MCRC, will be borne by the Contractor.

The MCRC will not pay the Contractor for the work performed on the projects until after the inspections are completed, corrective work is completed (if necessary), and the projects are accepted by the MCRC.

PROJECT QUANTITIES AND INVOICING REQUIREMENTS

The Contractor shall document and record the “As-built” quantities for the pay items for the project as the work is being performed.

The Contractor shall provide load tickets for materials placed (HMA, aggregate, etc.) on the project to the MCRC and/or their representatives.

“As-built” quantities will be verified by the MCRC and/or their representatives.

**Manistee County Road Commission
Bid Forms and Requirements for
High Bridge Road 2026**

Page 4 of 4

It is important for the Contractor to provide accurate documentation and invoices to the MCRC for review, consideration, and processing.

MEASUREMENT AND PAYMENT:

The completed work, including all materials, labor, and equipment, as measured, will be paid for at the contract unit price for the items (pay items), as shown on the Itemized Bid Form.

COMPANY NAME: _____

COMPANY ADDRESS: _____

PHONE: _____ FAX: _____

EMAIL: _____

BIDDERS NAME AND TITLE: _____

BIDDERS SIGNATURE: _____

DATE: _____

The Board reserves the right to accept or reject any or all bids and to accept the bids it feels is in the best interest of the Manistee County Road Commission.

Date: 10/1/2026

Manistee County Road Commission Itemized Bid Form
Bids Due: Monday, October 12, 2026 at 1:00 PM

High Bridge Road 2026

Item Number	Item Description	Estimated Quantity	Unit	Unit Price	Amount
8070075	Guardrail, Salv	609	Ft		
2020004	Tree, Rem, 6 inch to 18 inch (132+50 RT)	6	Ea		
2020004	Tree, Rem, 6 inch to 18 inch (previously fallen)	16	Ea		
2020004	Tree, Rem, 6 inch to 18 inch (previously fallen)	3	Ea		
2020004	Tree, Rem, 6 inch to 18 inch (leaning)	22	Ea		
2050010	Embankment, CIP (new slope RT to 1:2)	4,336	Cyd		
2050016	Excavation, Earth (remove failed material)	884	Cyd		
2050010	Embankment, CIP (temp remove roadway)	8,297	Cyd		
2050016	Excavation, Earth (temp remove roadway)	8,686	Cyd		
3010002	Subbase, CIP (temp remove roadway)	389	Cyd		
2080036	Erosion Control, Silt Fence	355	Ft		
3070121	Shld, CI II	154	Ton		
3060010	Aggregate Surface Cse, 6 inch	1,747	Syd		
3020020	Aggregate Base, 8 inch	1,747	Syd		
5010005	HMA Surface, Rem	1,686	Syd		
8070044	Guardrail Approach Terminal, Type 2M	1	Ea		
8072180	Guardrail, Type MGS-8, 108 inch Post	770	Ft		

Manistee County Road Commission Itemized Bid Form
Bids Due: Monday, October 12, 2026 at 1:00 PM

High Bridge Road 2026

Item Number	Item Description	Estimated Quantity	Unit	Unit Price	Amount
4040013	Underdrain, Bank, Open-Graded, 6 inch	131	Ft		
4040113	Underdrain, Outlet Ending, 6 inch	1	Ea		
8130010	Riprap, Plain	53	Syd		
8162004	Slope Restoration, Non-Freeway, Type D	1,907	Syd		
8162003	Slope Restoration, Non-Freeway, Type C	30	Syd		
8162006	Slope Restoration, Non-Freeway, Type F	143	Syd		
2050043	Subgrade Undercutting, Type IV	1,203	Cyd		
3080010	Geotextile, Separator, Non-Woven	1,283	Syd		
8100371	Post, Steel, 3 pound	39	Ft		
8102010	Ground Mtd Sign Support, Rem	3	Ea		
8102003	Sign, Type III, Rem, Salv	6	Ea		
8100402	Sign, Type III, Erect, Salv	6	Ea		
Above Items Failed Fill Slope					
2010001	Clearing	0.20	Acre		
2050010	Embankment, CIP	596	Cyd		
2050016	Excavation, Earth	326	Cyd		
4040013	Underdrain, Bank, Open-Graded, 6 inch	150	Ft		
4040003	Underdrain, Bank, 6 inch	300	Ft		
2057011	_Geocellular Confinement System	385	Syd		
8162003	Slope Restoration, Non-Freeway, Type C	936	Syd		
Above Items Failed Cut Slope					
2010001	Clearing	0.20	Acre		
2050016	Excavation, Earth	72	Cyd		
2057011	_Geocellular Confinement System	324	Syd		
8162003	Slope Restoration, Non-Freeway, Type C	647	Syd		
Above Items Flatten Cut Slope					

Manistee County Road Commission Itemized Bid Form
Bids Due: Monday, October 12, 2026 at 1:00 PM

High Bridge Road 2026

Item Number	Item Description	Estimated Quantity	Unit	Unit Price	Amount
8070075	Guardrail, Salv	229	Ft		
8072180	Guardrail, Type MGS-8, 108 inch Post	436	Ft		
2050020	Granular Blanket, Type 1	30	Cyd		
8162003	Slope Restoration, Non-Freeway, Type C	24	Syd		
2080036	Erosion Control, Silt Fence	596	Ft		
2050016	Excavation, Earth (for Rem material to 14" depth)	233	Cyd		
5010005	HMA Surface, Rem (full width)	1,531	Syd		
3087011	_Geotextile, Separator - Modified	3,410	Syd		
2050010	Embankment, CIP (for adding geotextile LT)	1,564	Cyd		
2050016	Excavation, Earth (for adding geotextile LT)	1,872	Cyd		
3010002	Subbase, CIP (for adding geotextile LT)	308	Cyd		
3070121	Shld, CI II	144	Ton		
3070121	Shld, CI II	36	Ton		
3070200	Trenching	5	Sta		
3060010	Aggregate Surface Cse, 6 inch	892	Syd		
3020020	Aggregate Base, 8 inch	892	Syd		
2030002	Culv, Rem, 24 inch to 48 inch	1	Ea		
2030001	Culv, Rem, Less than 24 inch	3	Ea		
4010541	Culv, CI E, 18 inch	88	Ft		
4010795	Culv, Downspout, 12 inch	38	Ft		
4010542	Culv, CI E, 24 inch	56	Ft		
4010049	Culv End Sect, Conc, 18 inch	1	Ea		
4010051	Culv End Sect, Conc, 24 inch	1	Ea		
4030210	Dr Structure, 48 inch dia	1	Ea		
4030250	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	2.5	Ft		
4030035	Dr Structure Cover, Type E	1.0	Ea		

Manistee County Road Commission Itemized Bid Form

Bids Due: Monday, October 12, 2026 at 1:00 PM

High Bridge Road 2026

Item Number	Item Description	Estimated Quantity	Unit	Unit Price	Amount
2050010	Embankment, CIP (fill eroded trench)	100	Cyd		
8130010	Riprap, Plain	62	Syd		
2050006	Ditch Cleanout (var width)	2	Sta		
8162004	Slope Restoration, Non-Freeway, Type D	30	Syd		
8162004	Slope Restoration, Non-Freeway, Type D	196	Syd		
8162003	Slope Restoration, Non-Freeway, Type C	990	Syd		
8100371	Post, Steel, 3 pound	39	Ft		
8102010	Ground Mtd Sign Support, Rem	3	Ea		
8102003	Sign, Type III, Rem, Salv	6	Ea		
8100402	Sign, Type III, Erect, Salv	6	Ea		
Above Items SB Lane					
1100001	Mobilization, Max (\$100,000.00)	1	LSUM		
2050016	Excavation, Earth (misc quant for exploratory trenching)	100	Cyd		
2050011	Embankment, LM	100	Cyd		
8127051	_Traffic Control (barrels, minor traf devices etc)	1	LSUM		
8162003	Slope Restoration, Non-Freeway, Type C	500	Syd		
Above Misc Items					
				Total Bid:	

ALTERNATE BID #1

Replace the **4G** material shown in the bottom of Subgrade Undercutting, Type IV with **3x6 Crushed Stone**. Delete the 2050043 item and add this 2057021 Item. All other pay items remain the same.

Item Number	Item Description	Estimated Quantity	Unit	Unit Price	Amount
2057021	Subgrade Undercutting, Type IV - Modified	1,203	Cyd		
				Total Bid:	

Manistee County Road Commission Itemized Bid Form
Bids Due: Monday, October 12, 2026 at 1:00 PM

High Bridge Road 2026

Company Name: _____

Company Address: _____

Bidders Name and Title: _____

Bidders Signature: _____

Email Address: _____

Date: _____

The Board reserves the right to accept or reject any or all bids and to accept the bids it feels is in the best interest of the Manistee County Road Commission.

Bids may be extended for additional years with mutual agreement.

Prepared By:

Manistee County Road Commission
8946 Chippewa Highway
Bear Lake, MI 49614
Phone: 231.889.0000

Date: 10/01/26